







**POLE SCHEDULE**

POLE #	TYPE	UNITS	REMARKS
A-1	A	6	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
A-2	A	6	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
B-1	A	10	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
B-2	A	10	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
C-1	A	4	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
C-2	A	4	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
C-3	A	4	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
C-4	A	4	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
D-1	B	2	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL
D-2	B	2	LAMP HODDERS - 1000WATT - SHADA # 106-637 OR EQUAL

**GENERAL NOTES**

CONTRACTOR SHALL VERIFY SITE CONDITIONS AND DIMENSIONS BEFORE STARTING WORK.  
 CONCRETE FOUNDATIONS SHALL BE CLASS A.  
 POLES SHALL BE DELIVERED TO JOB SITE DOWNSIDE TWO CODES VALBUENA 190 ALUMINUM. PAINT SHALL BE APPLIED BEFORE ERECTION.  
 UNDERGROUND PIPE SYSTEMS OF RECORD SHALL BE MAINTAINED AND CONTRACTOR SHALL USE CAUTION WHEN EXCAVATING TO AVOID DAMAGE TO WATER SYSTEM.

APPROVED: [Signature] 1982  
 CITY ENGINEER  
 REGISTERED CIVIL ENGINEER NO. 12345  
 DRAWING NO. 3998  
 CHECKED BY: [Signature]  
 RECOMMENDED BY: [Signature]  
 SAN BERNARDINO, CALIFORNIA