Notes:
1. All work embodied on these plans, to be done in conformity with applicable provisions of specifications No. 221.
2. Exact locations of sewer laterals to be determined in the field.
3. Manhole frames and covers to be constructed 6" below official street grades by sewer contractor. Paving contractor to adjust frames and cover to official grades after paving.

Profile Top of North Curb
Profile Top of East Curb
Profile Crown Line
Profile Top of West Curb
E. P. 12' N.
E. P. 12' S.
℄ Exist. Pavement
℄ 48TH ST.
℄ 49TH ST.
℄ E' ST.
STODDARD AVE.
Const. Std Type "D" Cross Gutter
Const. Std Type "A" Manhole
Const. Std Type "G" Manhole
Const. 8" V.C. Sewer
Const. Std Type "A" Section
Const. Curb & Gutter per Section
Const. 4' Std. Sidewalk
Const. 2½" Bituminous P.M.S.
Construct 2½" Bituminous P.M.S. between Gutter & Exist. Surfacing
Construct 4" Conc. Sidewalk
Construct 2½" Bituminous Plant-Mixed Surfacing
Construct Laterals to Property Lines
Prop. Line
Exist. Surfacing
Variable
Level
Slope ¼"=1'
Const. Type "B" Curb & Gutter
Const. 2½" Bituminous Plant-Mixed Surfacing

SECTION D-D
Scale: Horiz.: 1"=10'
Vert.: 1"=2'

SECTION C-C
Scale: Horiz.: 1"=10'
Vert.: 1"=2'