SPECIFICATION NO. 712 A.

SPECIFICATIONS FOR THE CONSTRUCTION OF A STARTER SHOE FOR WELL NO. 1, DEVIL CANYON PROJECT.

The work herein provided for is to be done in accordance with the plans and to these specifications.

WORK,

The work shall include the furnishing of all labor and material necessary to perform said work and do whatever else is required by the specifications.

Steel shall consist of medium steel plate, rolled and sheared according to best mill practice, shall have a tensile strength of not less than 55,000 pounds to the square inch and an elastic limit of not less than 35,000 pounds per square inch and shall show no signs of fracture when bent to the shape shown on the plans.

Riveting rivets shall be spaced evenly and the spacing and size to be such as will allow seventy per cent of the strength of the material.

The price bid shall be for the starter shoe complete F.O.B. San Bernardino, California.

The contractor shall furnish the City Engineer with full access to all work during the process of making the shoe.

Whenever the word "Contractor is used in these specifications it refers to the parties of the second part in the agreement for the construction of the work herein specified.

Whenever the word "City Engineer" is used in these specifications it refers to the City Engineer of the City of San Bernardino.

Schedule of Payments.

Payment will be made for the work as follows:

When the City Engineer shall certify to the Mayor and Common Council that the work has progressed in accordance with the plans and specifications for said work as follows:

1. When the starter shoe is delivered and accepted as shown on these specifications, seventy-five per cent (75%) of the amount bid on said Item.

2. Thirty-five days after completion and acceptance twenty-five per